

## **Handling Instructions for Your Order**

### **Production and Loading**

Your panels were manufactured to precise standards and stacked directly out of the machine into a clean, organized bundle. The stack was then carefully loaded by forklift onto the delivery truck. This minimizes the chance of scratches or defects during production and transport.

### **Unloading at Delivery**

When offloading, lift the sheets straight up rather than sliding them across one another. Sliding can cause edge damage and surface scratches. We recommend removing only a few sheets at a time, with one person on each side of the panel to ensure proper handling. Protective gloves (garden or work gloves) are strongly recommended, as panel edges can be sharp.

### **Preventing Damage**

Be aware that the sheet edges can act like a key, cutting through paint or finish if dragged across another surface. Each stack includes a protective top and bottom sheet. These are intended to shield your order during transit and may be discarded once unloading is complete.